

























MODEL 211.004 /006 /016 /026 /042 /043 /061 /065 /070 1# except CODE (924) Bivalent natural gas drive Vehicles up to model year 2003 (code 803) with Audio 20 CC radio






















A40/3 COMAND operating, display and control unit
N41/1 Navigation processor



P82.86-4627-06

	Check		
1	Check control unit versions of MOST components.	Make sure that an updated replacement for the MOST components to be replaced is available in order to be able to operate the COMAND.	AN82.85-P-0003-01T
AD	Connect STAR DIAGNOSIS and read out fault memory	STAR DIAGNOSIS diagnosis system	AD00.00-P-2000-04A *WE58.40-Z-1013-06A
	Remove		
	Notes on avoiding damage to electronic components due to electrostatic discharge		AH54.00-P-0001-01A
2.1	Remove all CDs from CD changer	Vehicles with CD changer (code 819).	
3	Remove all cassettes from Audio 20 CC radio		
Danger!	Risk of explosion caused by oxyhydrogen gas. Risk of poisoning and caustic burns caused by swallowing battery acid. Risk of injury through burns to skin and eyes from battery acid or when handling damaged lead-acid batteries Disconnect battery ground cable	No fire, sparks, open flames or smoking. Wear acid-resistant gloves, clothing and safety glasses. Pour battery acid only into suitable and appropriately marked containers.	AS54.10-Z-0001-01A
4	Notes on battery Notes on mat battery		AR54.10-P-0003T AH54.10-P-0001-01A AH54.10-P-0002-01A
AR	Remove side paneling in trunk	Left For vehicles without one of the following codes: - 220, 404, 405, 433, 434, 475, 550 or 889 the trim is no longer required and replaced by a new one. Vehicles without through-loading feature (code 287). Vehicles with through-loading feature (code 287).	AR68.30-P-4800T AR68.30-P-4800TA
AR	Remove SAM control unit with fuse and relay box in trunk	Do not disconnect electrical connectors.	AR54.21-P-1258T
7	Remove audio gateway control unit Remove audio component center	The audio gateway control unit has to be replaced by a new one for the COMAND APS (with navigation) (code 527).	AR82.60-P-7605T
AR			

8.1	Remove hands-free system control unit	<p> Only remove the hands-free system control unit if it has an MB number, which is given in the table of the document listed in step 1.</p> <p> Vehicles with preinstallation for MB phone "CTEL ", complete (code 380) or with MB "portable CTEL" in armrest (code 382).</p>	AR82.70-P-8970T
9.1	Remove car interface (portable CTEL)	<p> Only remove the truck interface (portable CTEL) if it has an MB number, which is given in the table of the document listed in step 1.</p> <p> Vehicles with preinstallation for MB phone "CTEL ", complete (code 380) or with MB "portable CTEL" in armrest (code 382).</p>	AR82.70-P-8920T
10.1	Remove CD changer	<p> Only remove the CD changer if it has an MB number, which is given in the table of the document listed in step 1.</p> <p> Vehicles with CD changer (code 819).</p>	AR82.64-P-7508T
11	Remove radio	 The Audio 20 CC radio is no longer required.	AR82.60-P-7502T
12	Remove instrument cluster	 Vehicles without heat-insulating glass (code 596).	AR54.30-P-6015T
13	Remove front floor covering (left)	 Vehicles without heat-insulating glass (code 596).	AR68.20-P-2050T
14	Remove trim on left B-pillar	<p> Undo in lower area until the cable duct is accessible.</p> <p> Vehicles without heat-insulating glass (code 596).</p>	AR68.30-P-4700T
15.1	Remove rear seat cushion	<p> Vehicles without heat-insulating glass (code 596).</p> <p> Vehicles without through-loading feature (code 287).</p>	AR91.12-P-1020T
15.2	Unlock rear seat cushion and set to upright position	<p> Vehicles without heat-insulating glass (code 596).</p> <p>Vehicles with through-loading feature (code 287).</p>	
16	Remove side cushion on left rear seat backrest	 Vehicles without heat-insulating glass (code 596).	
17	Open left wiring ducts	 Vehicles without heat-insulating glass (code 596).	
18.1	Remove antenna	<p> Vehicles with heat-insulating glass (code 596) and antenna for telephone (D- and E-networks) (code 354).</p> <p>Antenna is no longer required</p>	AR82.70-P-8951TE
	Install		
19	Installing antenna	<p> Vehicles with heat-insulating glass (code 596).</p> <p>Use new antenna for COMAND APS (with navigation) (code 527).</p> <p>The line clip for the GPS antenna connector (A2/49a2x1) have to be retrofitted.</p> <p> On vehicles without telephone (D- and E-networks) antenna (code 354), the line clip for the telephone antenna connector (A2/49a1x1) has to be retrofitted.</p> <p>Window cleaning agent Glass primer</p>	AR82.70-P-8951T *BR00.45-Z-1029-04A *BR00.45-Z-1027-02A
20.1	Retrofit antenna for global positioning system (GPS)	 Vehicles without heat-insulating glass (code 596).	AN82.61-P-7474-04TTS
21	Install in the reverse sequence	 Steps 17 to 12 and 9.1 to 8.1.	
22	Install audio gateway control unit Install central audio component	 Use new audio gateway control unit for COMAND APS (with navigation) (code 527).	AR82.60-P-7605T

23	Extend fiber optic cable ring for components to be retrofitted	 Risk of breakage! Do not kink fiber optic cable, route over sharp edges or bend in radii smaller than 25 mm. Tensile forces on inserts must not exceed 65 N. Do not squeeze fiber optic cable and do not compress with clamps or tie straps.	AN82.64-P-0001-05T
24	Retrofit wiring harness	 Wiring harness for navigation processor.  Vehicles without heat-insulating glass (code 596).  Vehicles with heat-insulating glass (code 596).	AN82.61-P-0001-01TCC AN82.61-P-0001-01TDD
25	 AR Install SAM control unit with fuse and relay box in trunk		AR54.21-P-1258T
26	Retrofitting navigation processor in trunk	 Vehicles with one of the following codes: - 220, 475 or 889.  Vehicles without one of the following codes: - 220, 475 or 889.	AN82.85-P-0001-01TA AN82.85-P-0001-01TTA
27.1	 Cut out side paneling in trunk	 Vehicles with one of the following codes: - 220, 404, 405, 433, 434, 475, 550 or 889.	AN68.30-P-0002-02TA
28	 AR  AR Install side paneling in left side of trunk	Vehicles without through-loading feature (code 287). Vehicles with through-loading feature (code 287).	AR68.30-P-4800T AR68.30-P-4800TA
29	 AR Install COMAND operating, display and control unit		AR82.85-P-1000T
30.1	 AR Install CD changer	 Vehicles with CD changer (code 819).  Only install the CD changer, if it was removed in step 10.1.	AR82.64-P-7508T
31	 AR Connect ground cable to battery		AR54.10-P-0003T
32	 AR Perform basic programming		AR00.19-P-0200T
33.1	 AR Flash MOST components Control unit flashing	 Flash MOST components that do not have the latest software release. STAR DIAGNOSIS diagnosis system.	AR54.21-P-0012Y *WE58.40-Z-1013-06A
34	Perform version coding subsequently	 After completing the variant coding run a quick test and clear the fault memory. STAR DIAGNOSIS diagnosis system.	AN82.61-P-0001-05TB *WE58.40-Z-1013-06A
35	Carry out function check of COMAND		
36	Add special equipment to the vehicle data card and to the online vehicle data card	 Enter COMAND APS (with navigation) (code 527) and delete MB Audio 20 CC radio (code 523). Delete old radio identification code and enter new one.	

Workshop equipment/MB testers (see Workshop Equipment Manual)

WE58.40-Z-1013-06A	STAR DIAGNOSIS Compact diagnosis system for passenger cars, order number 6511 1801 00
--------------------	---

Auxiliary repair materials

Number	Designation	Order number
BR00.45-Z-1027-02A	Glass primer	006 989 39 71
BR00.45-Z-1029-04A	Window cleaning agent	005 989 19 71

Parts ordering notes

Part no.	Designation	Quantity
B6 782 35 52	COMAND APS retrofit kit	1
A211 693 01 17	Covering for left luggage compartment (only required for vehicles up to chassis end number A 644804 or X170410 with one of the following listed codes: 220/404/405/433/434/475/550/889)	1
A211 690 01 53	Left trunk lining for vehicles up to chassis end number A 644804 or X170410 with code 287 (only required for vehicles without one of the following codes: 220/404/405/433/434/475/550/889)	1
A211 690 99 25	Left trunk lining for vehicles up to chassis end number A 644804 or X170410 without code 287 (only required for vehicles without one of the following codes: 220/404/405/433/434/475/550/889)	1

A211 690 87 53	Left trunk lining for vehicles as of chassis end number A 644805 or X170411 with code 287 (only required for vehicles without one of the following codes: 220/404/405/433/434/475/550/889)	1
A211 690 79 53	Left trunk lining for vehicles as of chassis end number A 644805 or X170411 without code 287 (only required for vehicles without one of the following codes: 220/404/405/433/434/475/550/889)	1
A211 545 63 40	Bracket (only required for vehicles without one of the following listed codes: 220/475/550/889)	1
N910 112 006 003	M6 nut (only required for vehicles without one of the following listed codes: 220/475/550/889)	1
N910 143 006 000	M6x12 bolt (only required for vehicles without one of the following listed codes: 220/889)	1
A211 820 35 75	GPS antenna (only required for vehicles with code 596)	1
A000 995 04 14	Line clip (only required for vehicles with code 596)	1
A000 995 04 14	Line clip (only required for vehicles with code 596 and without code 354)	1
B6 782 31 00	GPS antenna (only required for vehicles without code 596)	1
A211 540 10 10	GPS antenna line (only required for vehicles without code 596)	1
KG82 (see EPC)	Audio gateway control unit for code 527	1
KG82 (see EPC)	Hands-free system control unit (only required if it has to be replaced according to step 1)	1
KG82 (see EPC)	Truck interface portable CTEL (only required if it has to be replaced according to step 1)	1
KG82 (see EPC)	CD changer (only required if it has to be replaced according to step 1)	1
A000 983 89 10	Self-adhesive felt strip	As required
A005 997 62 90	Tie strap	As required